



Transcontinental Gas Pipe
Line Company, LLC
2800 Post Oak Boulevard
Houston, Texas 77056

April 19, 2019

Re: Transcontinental Gas Pipe Line Company, LLC
Proposed Rivervale South to Market Project (Project)
Federal Energy Regulatory Commission (FERC) Docket Number: CP17-490

Dear Neighbor,

Williams has made a change to the original dates on our previous letter. We apologize for the inconvenience. There will be no other date changes concerning this test.

In your area, Williams is currently upgrading existing facilities for the uprate of our North New Jersey Extension, a 10.35 mile, 24-inch lateral pipeline that is part of the Transco system located in Bergen County.

This letter is to advise you Transco will be performing pipeline safety testing on approximately a 10.35 mile, 24-inch North New Jersey Lateral pipeline in your area beginning on May 4th and ending May 6th. Any gas service you have to your home will not be affected by this test.

This safety testing is known as a hydrostatic test and is a common industry procedure designed to ensure the safety and integrity of the pipeline. The procedure involves taking sections of the line out of service, filling it with water, and slowly pressurizing it to levels higher than the normal operating pressure in order to verify the strength of the pipe and to identify any potential weaknesses in the line. The total test cycle for each section, including increasing and reducing the pressure, will take approximately 15 hours. The pipeline will be continuously monitored during the testing period and you may see Williams personnel and/or contract workers on the pipeline right of way.

Your property is located on a section of the test. Williams, in an abundance of caution, is requesting the general public to remain clear of the pipeline right of way when possible during the testing period (May 4th-6th). In the event a problem occurs during a hydrostatic test, pipeline personnel will identify the location of the release and make repairs. More populated areas may have barricades, warning signs, and personnel on site requesting the public to remain clear of those areas. Once the hydrostatic test is complete, any barricades and signs will be removed from that section. Upon successful completion of the entire 10 mile test the pipe will be placed back into service.

Transco's North New Jersey Lateral is being tested through Rivervale, Paramus and Emerson Townships. The Emergency Responders in each township will be notified of the testing schedule.

For more information on hydrostatic test procedures please visit www.ingaa.org/hydrotest.

Thank you in advance for your cooperation as we perform this necessary maintenance. If you have questions or concerns, please call 800-517-0119 and leave your contact information and concern. You can also reach your local land agent Wassim Saad by the number below.

Sincerely,

August Nicolaus
Land Representative

Contract Land Agent: Wassim Saad (508) 328-1346